

E.PROTECT WALL FOR HYDROSTATIC WATERPROOFING AND VAPOR INTRUSION MITIGATION SPECIFICATION

SECTION 02 56 16 – GAS CONTAINMENT

SECTION 02 56 19.13 – FLUID-APPLIED GAS BARRIER

SECTION 07 14 16 – COLD FLUID-APPLIED WATERPROOFING

SECTION 07 17 16 – BENTONITE COMPOSITE SHEET WATERPROOFING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the contract, including general and supplementary conditions, and Division 1 specification section, apply to this section.

1.2 SECTION INCLUDES

- A. The installation of materials designed to provide below grade waterproofing and vapor intrusion protection when installed per project specification, this section covers the waterproofing and vapor intrusion membrane, along with the following:
 - 1. Surface preparation and substrate treatment
 - 2. Auxiliary materials
 - 3. Prefabricated drainage mat
 - 4. Foundation drain

1.3 RELATED SECTIONS

- A. Section 02 24 00: Environmental Assessment
- B. Section 02 32 00: Geotechnical Investigation
- C. Section 03 15 00: Concrete Accessories
- D. Section 03 30 00: Cast-in-Place Concrete
- E. Section 03 40 00: Precast Concrete
- F. Section 07 90 00: Joint Protection
- G. Section 31 30 00: Earthwork Methods
- H. Section 33 41 00: Subdrainage

1.4 PERFORMANCE REQUIREMENTS

- A. General: Provide a waterproofing system that prevents the passage of water under hydrostatic conditions, methane gas, contaminant vapor, and complies with the physical requirements as demonstrated by testing performed by an independent testing agency.

1.5 SUBMITTALS

- A. Product Data: For each type of waterproofing specified submit manufacturer's printed technical data, tested physical and performance properties, instructions for evaluating, preparing, and treating substrates, and installation instructions.
- B. Shop Drawings: Project specific drawings showing locations and extent of waterproofing, details for substrate joints and cracks, sheet flashing, penetrations, transitions, and termination conditions.
- C. Samples: Submit two standard size samples of the of the following:
 - 1. Individual components of the specified composite membrane system.
- D. Applicator Certification: Submit written confirmation at the time of bid that applicator is currently approved by the membrane manufacturer.

1.6 QUALITY ASSURANCE

- A. Applicator Qualifications: Waterproofing applicator shall be an EPRO Authorized Applicator who is trained and performs work that in accordance with EPRO standards and policies. For project requiring a no-dollar-limit labor and material warranty, the waterproofing applicator must be E.Assurance Certified at the time of bid.
- B. Third Party Inspection: Independent inspection of the composite system installation may be required based on project conditions and desired warranty coverage. Inspection reports shall be submitted directly to the composite waterproofing manufacturer and made available to other parties per the owners' direction. For projects requiring a no-dollar-limit labor and material warranty, an independent inspector must be E.Assurance Certified and comply with the documentation requirements.
- C. Water Sample: A 2-liter representative ground water sample shall be sent by the installation contractor to the manufacturer if contaminated groundwater and/or salt water has been discovered on the site. Email Watersample@eproinc.com to receive shipping instructions.
- D. Pre-Construction Meeting: A meeting shall be held prior to application of the waterproofing system to assure proper substrate preparation, confirm installation conditions, and any additional project specific requirements. Attendees of the meeting shall include, but are not limited to the following:
 - 1. EPRO representative
 - 2. EPRO certified applicator
 - 3. Third party inspector
 - 4. General contractor
 - 5. Owners representative
 - 6. Concrete/Shotcrete contractor
 - 7. Rebar contractor
 - 8. Project design team
 - 9. All appropriate related trades
- E. Field Sample: Apply waterproofing system field sample to 100 ft² (9.3 m²) of each assembly to demonstrate proper application techniques and standard of workmanship.

1. Notify composite membrane system manufacturer representative, architect, certified inspector, and other appropriate parties one week in advance of the dates and times when field sample will be prepared.
2. If architect and certified inspector determine that field sample does not meet requirements; reapply composite membrane system until field sample is approved.
3. Retain and maintain approved field sample during construction in an undisturbed condition as a standard for judging the completed composite membrane system. An undamaged field sample may become part of the completed work.

F. Materials: Composite membrane system and auxiliary materials shall be single sourced.

1.7 MATERIAL DELIVERY, STORAGE AND DISPOSAL

- A. Delivery: Deliver materials to site labeled with manufacturer's name, product brand name, material type, and date of manufacture. Upon the arrival of materials to the jobsite, inspect materials to confirm material has not been damaged during transit.
- B. Storage: Proper storage of onsite materials is the responsibility of the certified applicator. Consult product data sheets to confirm storage requirements. Storage area shall be clean, dry, and protected from the elements. If ambient air temperatures are expected to fall below 40°F, precautions will need to be taken to protect any polymer modified asphalt product from near freezing temperatures. Protect stored materials from direct sunlight.
- C. Disposal: Remove and replace any material that cannot be properly applied in accordance with local regulations and specification section 01 74 19.

1.8 PROJECT CONDITIONS

- A. Substrate Review: Substrates shall be reviewed by the certified applicator and accepted by the certified inspector prior to application. Application without signoff from certified inspector will likely result in voidance of warranty.
- B. Penetrations: All plumbing, electrical, mechanical, and structural items to be passing through the composite membrane system shall be properly spaced, positively secured in their proper positions, and appropriately protected prior to system application and throughout the construction phase. Braided grounding rods are not allowed to pass through the membrane in waterproofing applications.
- C. Clearance: Minimum clearance of 24 inches is required for application of spray applied polymer modified asphalt, **e.spray**. For areas with less than 24-inch clearance, the **e.spray** membrane may be applied by hand using **e.roll**.
- D. Overspray: Protect all adjacent areas not receiving **e.spray** or **e.roll**. Masking is necessary to prevent unwanted overspray from adhering to, or staining, areas not receiving the membrane. Once **e.spray** or **e.roll** adheres to a surface it is extremely difficult to remove.
- E. Weather Limitations: Perform work only when existing and forecast weather conditions are within manufacturer's recommendations.
 1. Spray Applied Polymer Modified Asphalt Membrane: Minimum ambient temperature must be 40°F (7°C) and rising. For applications temperatures below 38 degrees, but greater than +19°F/-7°C, special equipment and material handling is needed. Substrate shall be clean and free from standing moisture.

2. EPRO applicators reserve the right not to install product when application conditions might be within manufactures acceptance, but ambient conditions may limit a successful application.
3. Bentonite: Application of bentonite materials to damp surfaces is acceptable provided it is being installed over **e.spray**.

1.9 WARRANTY

- A. General Warranty: The special warranty specified in this section shall not deprive the owner of other rights the owner may have under other provisions of the contract documents, and shall be in addition to, and run concurrent with, other warranties made by the contractor under requirements of the contract documents.
- B. Special Warranty: Submit a written warranty signed by waterproofing manufacturer agreeing to replace system materials that do not conform with manufactures published specifications, or are deemed to be defective. Warranty does not include failure of waterproofing due to failure of soil substrate prepared and treated according to requirements or formation of new joints and cracks in the specially applied concrete that exceed 1/8 inch (3.175 mm) in width.
 1. Warranty Period: 5 years after date of substantial completion. Longer warranty periods are available upon request.
 2. Coverage: Manufacturer will guarantee that the material provided is free of defects for the warranty period.
- C. Additional Warranty Options: Upgraded warranties are available by contacting the manufacturer. These warranties may have additional requirements and approval must be granted in accordance to the manufacturer's warranty requirements. Additional warranty options include:
 1. Standard Labor and Material (E.Series L&M): Manufacturer will provide non-prorated coverage for the warranty term, agreeing to repair or replace material that does not meet requirements or remain watertight.
 2. No-Dollar-Limit Labor and Material Warranty (E.Assurance NDL): Manufacturer will provide a non-prorated, no-dollar-limit, coverage for the warranty term, agreeing to repair or replace material that does not meet requirements or remain watertight.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturer: EPRO Services, Inc. (EPRO), P.O. Box 347; Derby, KS 67037; Tel: (800) 882-1896; Email: Info@eproinc.com; Web: www.eproinc.com
- B. Cast-in-Place Walls: E.Protect Wall (95 mils) – **e.spray** (80 mils), **e.shield 115**, **e.drain 6000**

2.2 SYSTEM PHYSICAL PROPERTIES

- A. The physical properties listed in this section reflect testing on the entire composite system. Physical properties of the individual system composite can be found in Specification Section 2.3.

1. **E.Protect Wall** composite system consists of 80 mil layer of **e.spray** (polymer modified asphalt membrane), and **e.shield 115** (15 mil polyolefin protection layer). Designed to handle a wide variety of positive side wall conditions, while providing enhanced protection against common backfill materials.

PROPERTIES	TEST METHOD	VALUE
Tensile Strength	ASTM D412	1027.7 psi
Elongation	ASTM D412	664%
Adhesion to Concrete	ASTM D903	20.0 lbf/in
Puncture Resistance	ASTM D1709	57.2 lbf
Hydrostatic Head Resistance	ASTM D5385	100 psi (231 ft)
Water Vapor Transmission	ASTM E96	.0374 perms

2.3 WATERPROOFING MATERIALS

- A. Polymer Modified Asphalt

1. **e.spray**: **e.spray** is a non-hazardous, low-viscosity, water-based, anionic asphalt emulsion modified with a blend of synthetic polymerized rubbers and proprietary additives. **e.spray** is highly stable during transit and proper storage, but becomes highly reactive during the spray application to form a rapidly cured membrane with exceptional bonding, elongation, and hydrophobic characteristics.

PROPERTIES	TEST METHOD	VALUE
Color		Brown to Black
Solvent Content		No Solvents
Shelf Life		6 Months
Tensile Strength	ASTM D412	32 psi
Elongation	ASTM D412	4140%
Resistance to Decay	ASTM E154 Section 13	4% Perm Loss
Accelerated Aging	ASTM G23	No Effect
Moisture Vapor Transmission	ASTM E96	0.026 g/ft ² /hr
Hydrostatic Water Pressure	ASTM D751	26 psi
Perm Rating	ASTM E96	0.21 perms
Methane Transmission Rate	ASTM D1434	0
Adhesion to Concrete & Masonry	ASTM C836 & C704	20 lbf/inch
Adhesion to HDPE	ASTM C836	28.363 lbf/inch

Adhesion to Polypropylene Fabric	ASTM C836	31.19 lbf/inch
Hardness	ASTM C836	80
Crack Bridging	ASTM C836-00	No Cracking
Low Temp. Flexibility		No Cracking at -20° C
Packaging: 55 gallon drum, 275 gallon tote, 330 gallon tote		

2. **e.roll:** *e.roll* is a medium viscosity water-based, polymer-modified anionic asphalt emulsion, which exhibits exceptional bonding, elongation and waterproofing characteristics.

PROPERTIES	TEST METHOD	VALUE
Color		Brown to Black
Solvent Content		No Solvents
Shelf Life		6 Months
Tensile Strength	ASTM D412	32 psi
Elongation	ASTM D412	3860%
Resistance to Decay	ASTM E154 SECTION 13	9% Perm Loss
Accelerated Aging	ASTM G23	No Effect
Moisture Vapor Transmission	ASTM E96	0.071 g/ft ² /hr
Hydrostatic Water Pressure	ASTM D751	28 psi
Perm Rating	ASTM E96	0.17 perms
Methane Transmission Rate	ASTM D14334	0
Adhesion to Concrete & Masonry	ASTM C836	1 lbf/inch
Hardness	ASTM C836	85
Crack Bridging	ASTM C836	No Cracking
Low Temp. Flexibility	ASTM C836-00	No Cracking at -20° C
Packaging: 5 gallon bucket		

B. Polyolefin Sheet Membrane

1. **e.shield 115:** *e.shield 115* is a red 15 mil geomembrane made from a custom blend of polyolefin copolymers.

PROPERTIES	TEST METHOD	VALUE
Film Material		Polypropylene
Film Color		Red
Film Thickness		15 Mil
Classification	ASTM E1745	Class A, B & C
Water Vapor Permeance	ASTM F1249	0.0078 perms
Tensile Strength	ASTM D882	64 lbf./inch
Puncture Resistance	ASTM 1709	4000 grams
Life Expectancy	ASTM E154	Indefinite
Chemical Resistance	ASTM E154	Unaffected
Low Temp. Impact	ASTM D1790	Resistant to 105° C
Methane Gas Modified	ASTM D1434	252.55 GTR
ACI 302.1 R-96 Minimum Thickness 10-mils		Exceeds
Dimensions: 12' X 150'		
Weight: 144 pounds		

C. Prefabricated Drainage

1. **e.drain 6000:** *e.drain 6000* features a lightweight three-dimensional, high-compressive strength polypropylene core and bonded non-woven geotextile fabric. The bonded filter fabric allows water to pass freely into the molded drain while preventing soil particles from entering and clogging the core structure.

PROPERTIES	TEST METHOD	VALUE
DIMPLED CORE		
Core Material		Polypropylene
Color		Black
Dimple Height	ASTM D1777-96	0.4" (10.16 mm)
Compressive Strength	ASTM D6364-06	16,500 psf (790 kN/m ²)
Flow rate	ASTM D4716	21 gal/min/ft
FILTER FABRIC		
Grab Tensile	ASTM D4632-91	100 lbs
CBR Puncture resistance	ASTM D6241	250 lbs
Apparent Operating Size	ASTM D4751-99	70 sieve size (.0212 mm)
Water Flow Rate	ASTM D4491-99	140 gpm/ft ² (5704 l/min/m ²)
UV Resistance	ASTM D4355-92	70% (500 hrs)
Dimensions: 6' x 5'		
Weight: 63 pounds		

2. **e.drain 12ds:** *e.drain 12ds* features a lightweight three-dimensional, highly flexible polypropylene core and a non-woven geotextile filter fabric. The filter fabric is bonded to the dimples of the polypropylene core to prevent clogging within the drain.

PROPERTIES	TEST METHOD	VALUE
DIMPLED CORE		
Core Material		Polypropylene
Color		Black
Compressive strength	ASTM D1621	9,500 PSF (455 kN/m ²)
Thickness	ASTM D1777	1 Inch
Flow rate	ASTM D4716	30 gpm/ft of width
FILTER FABRIC		
CBR puncture	ASTM D6241	250 lbs
Grab tensile strength	ASTM D4632	100 lbs
AOS	ASTM D4751	70 U.S. sieve
Permitivity	ASTM D4491	2.0 sec ⁻¹
Flow rate	ASTM D4491	140 gpm/ft ²
UV resistance	ASTM D4355	70% (500 hrs)
Dimensions: 165' x 12" x 1"		
Weight: 65 pounds		

2.4 AUXILIARY MATERIALS

- A. General: All accessory products shall be provided by the specified waterproofing manufacturer. Auxiliary products used in lieu of, or in addition to, the manufacturer's products must be approved in writing by EPRO prior to installation.
- B. Reinforcement Fabric: Manufacturer's polyester fabric, **e.poly** is available in 6 inch, 12 inch, and 40 inch widths.
- C. Detailing Material: **e.roll**, a roller applied water based high viscosity polymer modified asphaltic material OR **e.trowel**, a trowel applied water based high viscosity polymer modified asphaltic material.
- D. Backer Rod: Closed cell polyethylene foam
- E. Water Stop: A double row **e.stop b** shall be placed at all cold joints, construction joints, penetrations, and steel beams in back lagged conditions. Water stop is not required at lift joints. A single row of **e.stop b** is acceptable at elevations above the design water table.
- F. Vertical Membrane Fastener: **e.hanger** with ¾ inch washer
- G. Termination Bar: **e.term hd**, or approved alternate
- H. Shot Pins: Minimum 1-inch galvanized steel pins with ¾ inch aluminum washer.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Comply with project documents, manufacturer's product information, including product application and installation guidelines, pre-job punch list, as well as, manufacturer's shipping and storage recommendations.

3.1.2 SURFACE PREPARATION

- A. The general contractor shall engage the certified waterproofing contractor and certified inspector to ensure surfaces are prepared in accordance with manufacturer's instructions. Unless, explicitly stated in the contract documents, the waterproofing contractor is not responsible for surface preparation.
- B. Examine all substrates, areas, and conditions under which the composite membrane system will be installed, applicator and inspector must be present. Do not proceed with installation until unsatisfactory conditions have been corrected and a surface prep requirements have been met. If conditions exist that are not addressed in this section notify inspector and contact EPRO for additional clarification.

- C. Cast-in-Place or Shotcrete Walls: Application to green concrete is acceptable provided the substrate is prepared in accordance with manufacturers specifications and published instructions.
1. Provide a clean, dust-free, and dry substrate for waterproofing application.
 2. Surfaces shall be power washed to remove grease, oil, form release agents or any other penetrating contaminants from the concrete. No agents shall be visible prior to the application of **e.spray**.
 3. Remove all fins, ridges, and other protrusions.
 4. Fill honeycomb, aggregate pockets, tie holes, and other voids with hydraulic cement, or rapid-set grout.
- D. Precast Concrete Walls:
1. Provide a clean, dust-free, and dry substrate for waterproofing application.
 2. Surfaces shall be power washed to remove grease, oil, form release agents, or any other penetrating contaminants from the concrete. No agents shall be visible prior to the application of **e.spray**.
 3. Remove all fins, ridges, and other protrusions.
 4. Fill honeycomb, aggregate pockets, tie holes, and other voids with hydraulic cement, or rapid-set grout. All grout should be struck smooth and without pinholes.
 5. Fill precast panel and control joints with a suitable backer rod material and sealant approved by manufacturer.
 6. Apply **e.roll** 3 inches horizontally and 3 inches vertically around the base of the penetration, including **e.stop b**.
 7. Embed reinforcement fabric 3 inches horizontally and 3 inches vertically around the base of the penetration.
 8. 6-inch reinforcement fabric is acceptable for most penetrations, but soil nails, rock anchors, and tiebacks (non-hydrostatic) will require 12-inch reinforcement fabric.

3.2 POSITIVE SIDE CONCRETE WALL INSTALLATION – E.PROTECT WALL

- A. General: The composite membrane system shall be installed to the positive side vertical wall under strict accordance with the manufacture’s guideline and project specifications. This section describes the installation process for the system application to a freestanding cast-in-place concrete or shotcrete wall.
- B. Green Concrete: Application to green concrete is acceptable. Ambient temperatures, humidity, and concrete mix ratio can create blistering. If applying the system within 7 days of concrete placement contact manufacturer for further instruction.

3.2.2 TREATMENT OF CRACKS, JOINTS, AND REPAIRED AREAS

- A. Treat, rout, and fill cracks larger than 1/8 inch with hydraulic cement or rapid set grout.
- B. The following areas shall receive a reinforcement detail of **e.roll** and reinforcement fabric:
1. All cracks less than 1/8 inch.

2. All previously repaired cracks.
 3. All cold joints.
- C. Reinforcement Detail: Apply a 30 mil coat of **e.roll** to desired area extending 3 inches beyond the joint or area of repair. Embed a joint reinforcing strip into the **e.roll**. Apply a second 30 mil coat of **e.roll** over **e.poly** reinforcement fabric ensuring full saturation.

3.2.3 DETAILING OF TRANSITIONS

- A. Corners: A reinforcement detail shall be applied to all transitions including all inside and outside corners, and all transitions from a horizontal to vertical planes.
- B. Underslab Transition: When the underslab composite membrane system transitions to a positive side concrete wall, the underslab system will terminate 2 feet above the slab to wall cold joint, or 2 feet above the design water table, whichever is greater.
- C. The underslab system will be fastened to the wall using **e.hanger**.
- D. Reinforcement Detail: Apply a 30 mil coat of **e.roll** to desired area extending 3 inches beyond the joint or area of repair. Embed a joint reinforcing strip into the **e.roll**. Apply a second 30 mil coat of **e.roll** over **e.poly** reinforcement fabric ensuring full saturation.

3.2.4 SEALING OF PENETRATIONS

- A. Standard Pipe Penetrations: Prepare membrane penetrations so they are free of any material that prohibit the material to bond directly to the penetration surface: foam, insulation, protective coatings, etc.
 1. Tightly wrap the penetration by pressing **e.stop b** firmly around the base of the penetration.
 2. Apply **e.roll** 3 inches horizontally and 3 inches vertically around the base of the penetration, including **e.stop b**.
 3. Embed **e.poly** reinforcement fabric 3 inches horizontally and 3 inches vertically around the base of the penetration.
 4. Apply a second layer of **e.roll** to the **e.poly** reinforcement fabric until the reinforcement fabric is fully saturated, and then secure the reinforcement fabric to the penetration with a cable tie.
 5. Cut a target piece of **e.poly** reinforcement fabric to the outside diameter of the penetration.
 6. Place target piece around the penetration and embed into existing saturated reinforcement fabric, saturate fabric with **e.roll**.

3.2.5 POLYMER MODIFIED ASPHALTIC MEMBRANE

- A. Mask off adjoining surfaces where unwanted **e.spray** polymer modified asphalt membrane may impact other construction trades.
- B. Commence application of **e.spray** when ambient air temperatures are within manufacturer recommendations.
- C. Surfaces that will receive **e.spray** must be sound, uniform, clean, and free from standing moisture.

- D. Start installing **e.spray** in presence of approved 3rd party inspector.
- E. Apply a 10 mil primer coat of un-catalyzed **e.spray** and allow to set. The primer coat is designed to reduce that amount of potential blistering that may occur as the concrete continues to release moisture.
- F. Moving from the low point to the high point of the wall, apply one application of **e.spray** in accordance with manufacturer's instructions in order to obtain a seamless membrane with a minimum dry film thickness of 80 mils (2 mm).
- G. Apply **e.spray/e.roll** in and around penetrations and cavities to ensure the formation of monolithic seal around all penetrations.
- H. Apply **e.spray/e.roll** to prepared wall terminations and vertical surfaces to heights indicated according to manufacturer's recommendations and details. (if applicable)
- I. Verify film thickness of **e.spray** every 1000 ft² (93 m²).

3.2.6 POLYOLEFIN PROTECTION COURSE

- A. Install **e.shield 115** protection course vertically or horizontally, either way is acceptable.
- B. Overlap **e.shield 115** seams a minimum 6 inches.
- C. Secure **e.shield 115** to **e.spray** with Sta'-Put Quick Grip LVOC spray adhesive, or approved alternate.
- D. Secure **e.shield 115** protection course seams with **e.tape**.

3.2.7 PREFABRICATED DRAINAGE MAT

- A. Horizontal Installation: Starting from one corner, run **e.drain 6000** horizontally along the base of the foundation.
 - 1. Secure drainage panels to the wall by using approved adhesives, adhesive strips, or fastened with shot pins or as recommended by manufacturer.
 - 2. Install the next layer of **e.drain 6000** in the same manner and overlap the next layer of drain mat 6 inches over the first layer of drain mat, thus creating a "shingle" effect. Continue this process to the top of the wall.
 - 3. Terminate the drainage and membrane system using a termination bar and a reinforcement detail.
 - 4. Care shall be taken when backfilling against the membrane in order to prevent any damage during the backfill process. Angular rock 1 inch or greater shall not be used without written approval from the manufacturer.
 - 5. Backfill in lifts, taking precaution to not backfill above the previously placed **e.drain 6000**.
- B. Vertical Installation: Starting from the top of wall, install **e.drain 6000** from the top of the wall to the base of the foundation.
 - 1. Overlap each roll of **e.drain 6000** 6 inches on all overlaps.
 - 2. Secure drainage composite panels to the wall by using by pressing drainage composite onto previously washered stick pins. Secure drainage composite by placing another stick pin washer over the drainage composite.

3. Secure **e.drain 6000** with a termination bar at the top of grade and no greater than 3 inches from the top of the drain.
 4. Secure **e.drain 6000** using approved adhesives.
- C. Geocomposite Strip Drain: If using **e.drain 12ds**, secure strip drain at the bottom of the footing or just above the design water table.
- D. Do not penetrate or damage the composite membrane system once it has been applied. If the system is penetrated or damaged, contact the applicator immediately. Failure to bring the breach of the system to the applicator's attention and not allowing adequate time to make the necessary repair will result in voiding any warranty.
- 3.2.8 TERMINATION AT TOP OF GRADE
- A. Termination at the top of grade shall be done with using at termination bar. Secure the termination bar every 12 inches on center and the center a reinforcement detail on the termination bar.
 - B. Reinforcement Detail - Apply a 30 mil coat of **e.roll** to desired area extending 3 inches beyond the joint or area of repair. Embed a joint reinforcing strip into the **e.roll**. Apply a second 30 mil coat of **e.roll** over **e.poly** reinforcement fabric ensuring full saturation.
- 3.3 FIELD QUALITY CONTROL
- A. Independent inspectors and certified applicators shall document the amount of **e.spray** used and document quantities in the inspection report.
- 3.4 CURING PROTECTING AND CLEANING
- A. Allow for **e.spray** to fully bond with the substrate, generally this occurs 24 to 48 hours after application depending on ambient weather conditions.
 - B. Take care to prevent contamination and damage during application stages and curing. All machinery, other trades, and general construction, shall NOT take place over the membrane until inspection is complete and concrete has been placed.
 - C. Prevent damage during the placement of overburden.
- 3.5 REPAIRS
- A. Concrete Walls:
 1. Inspect damaged area to determine which system components have been damaged.
 2. Only patch the areas that have been damaged by re-installing the damaged materials. The patch should extend 6 inches beyond the damaged area.

End of Section